BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT54209

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/18/2022-23, Date: 04-11-2022

Name of Work:Supply and Instalation of CCTV Cameras at Selected Points and maintenance of Existing CCTV Cameras in ward No. 09 Amruthahalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of BHARATH S ( )	
				In Figures	In Words
1	2.00	Outdoor PLZ IP Cameras with 20 X optical zoom with controller along with suitable mounting system (PTZ Pan Tilt and Zoom feature is availbale in this camera can be contolled by the software for pan Tilt and zoom feature at the contol center and can be programmed to view at different angles and zoom level continuosly. It operates at day and night and the viewing distance at clarity is about 100 metres Approved Data Rates	Nos	65751.16	Rupees Sixty Five Thousand Seven Hundred Fifty One and Sixteen Paise Only
2	12.00	Bracket (Corner Mount / Pole Mount/ Wall Mount) for mounting the PTZ camera.Approved Data Rates	Nos	3575.75	Rupees Three Thousand Five Hundred Seventy Five and Seventy Five
3	12.00	Outdoor 50 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 50 metres)Approved Data Rates	Nos	17732.08	Rupees Seventeen Thousand Seven Hundred Thirty Two and Eight Paise Only
4	12.00	Bracket and weatherproof Installation kit for 50 Meter IP Camera Approved Data Rates	Nos	1294.71	Rupees One Thousand Two Hundred Ninety Four and Seventy One Paise
5	10.00	Outdoor 30 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 30 metres)Approved Data Rates	Nos	12787.88	Rupees Twelve Thousand Seven Hundred Eighty Seven and Eighty
6	12.00	Bracket and weatherproof Installation kit for 30 Meter IP CameraApproved Data Rates	Nos	1249.46	Rupees One Thousand Two Hundred Forty Nine and Forty Six Paise Only
7	2.00	32 Channel NVR DS 7732 NI- E4 (with 4 Sata Option) the control box and the recording device to connect upto 32 devices, can be cascaded to provide additional cameras Approved Data Rates	Nos	56130.92	Rupees Fifty Six Thousand One Hundred Thirty and Ninety Two
8	2.00	12 TB NAS Box for Back up (NET GEAR) provides storage for the recorded data for quick view back and storage Approved Data Rates	Nos	215718.00	Rupees Two Hundred Fifteen Thousand Seven Hundred Eighteen Only
9	4.00	4 TB SATA for storage and fitted in the NVR Device for storage Approved Data Rates	Nos	19148.30	Rupees Nineteen Thousand One Hundred Forty Eight and Thirty
10	12.00	A suitable sheet metal control panel to house site Equipments (Weather Proof) The power supply and the ethernet connectivity adaptor is stored in this box.Approved Data Rates	Nos	1278.79	Rupees One Thousand Two Hundred Seventy Eight and Seventy Nine Paise Only
11	12.00	Power supply for the camera.Approved Data Rates	Nos	386.32	Rupees Three Hundred Eighty Six and Thirty Two Paise Only
12	12.00	Ethernet Switch for connectivity to Internet and Camera Approved Data Rates	Nos	796.10	Rupees Seven Hundred Ninety Six and Ten Paise Only
13	12.00	Supply & Laying of Network and Power Cables from Camera to the control Box. Approved Data Rates	Nos	325.99	Rupees Three Hundred Twenty Five and Ninety Nine Paise Only
14	10.00	Video Manager Application Software for Display and Management of Camera on Video Display.Approved Data Rates	Nos	16760.00	Rupees Sixteen Thousand Seven Hundred Sixty Only
15	12.00	Installation, Erection & commissioning chargesApproved Data Rates	Nos	4240.30	Rupees Four Thousand Two Hundred Forty and Thirty Paise Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು